

# Bluetooth® Low Energy (BLE) Module

#### **Features**

- · Qualified for Bluetooth SIG v4.2 specifications
- Certified to FCC, IC, MIC, KCC, NCC and SRRC radio regulations
- European R&TTE Directive Assessed Radio module
- · RoHS compliant
- · Supports UART interface
- · Supports transparent UART data service of BLE
- BM70 module supports 3-channel pulse-width modulation (PWM) and BM71 module supports 1-channel PWM
- Precision Temperature Sensor (PTS) for ambient temperature detection
- 12-bit ADC (ENOB=10 or 8 bits) supports for battery and voltage detection
- 8-channel ADC for BM70 module and 5-channel ADC for BM71 module are provided
- 18 general purpose I/O (GPIO) pins for BM70 module and 9 GPIO pins for BM71 module
- Integrated 32 MHz crystal
- · Small and compact surface mount module
- Castellated surface mount pads for easy and reliable host PCB mounting


#### **RF Features**

- ISM band 2.402 GHz to 2.480 GHz operation
- · Channels: 0-39
- Receive Sensitivity: typical -90 dBm (LE)
- Transmit Power: 0 dBm (typical)
- Received Signal Strength Indication (RSSI) monitor with 1 dB resolution

### MAC/Baseband/Higher Layer Features

- Secure AES128 encryption
- Bluetooth 4.2: GAP, GATT, SMP, L2CAP and integrated public profile
- Create custom GATT services, refer to the "BM70/ 71 Bluetooth® Low Energy Module User's Guide" (DS50002542) for details on creating GATT services
- I/O capability for Bluetooth 4.0/4.2 authentication
- Configurable role as peripheral/central, client/ server

#### FIGURE 1: BM70 MODULE



#### FIGURE 2: BM71 MODULE



#### **Antenna**

- Integrated chip antenna (BM7xBLES1FC2)
- External antenna connection through RF pad (BM7xBLE01FC2)

#### **Power Management**

- Two low-power modes supported, wake-up through GPIO or internal timer
- Average current: Tx=3.3 mA and Rx=3.2 mA with buck at 3.0V VBAT input and 18.75 msec connection interval.

### **Operating Conditions**

- · Operating voltage range: 1.9V to 3.6V
- Operating temperature: -40°C to +85°C

## BM70/71

## **Applications**

- · Internet of Things (IoT)
- · Payment or Security
- · Wearable Devices
- · Home and Security
- · Health and Fitness
- Beacons
- · Industrial and Data Logger

### **General Description**

The BM70/71 module offers BLE solution for embedded applications. It conforms to the Bluetooth core specification version 4.2 to enhance the throughput and security for the IoT applications. It also supports Beacon technology to enhance user experience for the IoT applications and enables users to control the cloud and receive data without opening the application through a smartphone.

The BM70/71 module has Bluetooth stack integrated and is available in different form factors to optimize the space, cost, and RF performance. The power-optimized design minimizes current consumption and extends battery life for portable and wearable applications.

#### **Table of Contents**

1.0 Device Overview	!
2.0 Application Information	13
3.0 Module Configuration	25
4.0 Antenna	27
5.0 Electrical Characteristics	
6.0 Physical Dimensions	43
7.0 Soldering Recommendations	51
8.0 Ordering Guide	53
Appendix A: Certification Notices	5
Annendix B: Revision History	61

#### TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

#### **Most Current Data Sheet**

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

#### http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000000A is version A of document DS30000000).

#### **Errata**

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- · Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

#### **Customer Notification System**

Register on our web site at www.microchip.com to receive the most current information on all of our products.



**NOTES:** 

#### 1.0 DEVICE OVERVIEW

The BM70/71 embedded 2.4 GHz Bluetooth 4.2 BLE module is built around Microchip Technology IS1870/71 BLE Integrated Circuit (IC). The IS1870/71 IC includes an on-board Bluetooth stack, a power management subsystem, a 2.4 GHz transceiver, and a RF power amplifier. The user can embed Bluetooth functionality into any end product using the BM70/71 module.

The BM70/71 module enables rapid product development and faster time to market. It is designed to provide simple Bluetooth solutions with the following features:

- · Simple integration and programming
- · Reduced development time
- · Superior wireless module with low-cost system
- Interoperability with Apple<sup>®</sup> iOS and Android™ OS
- · Wide range of applications

In addition, the BM70/71 module supports Beacon technology to improve the user experiences in IoT applications, such as auto connection/control and data to cloud.


The BM70/71 module can independently maintain a low-power wireless connection. Low-power usage and flexible power management maximize the lifetime of the BM70/71 module in battery operated devices. A wide operating temperature range enable its applications in indoor and outdoor environments.

The BM70/71 module is a small, compact, and surface-mounted module with castellated pads for easy and reliable host PCB mounting. The relatively small form factor of the module is targeted for applications, such as wearable sports, fitness devices and so on.

### 1.1 Interface Description


Figure 1-1 and Figure 1-2 illustrate an example of the BM70/71 module-based system.

FIGURE 1-1: BM70 MODULE-BASED SYSTEM BLOCK DIAGRAM



**Note 1:** It is possible to enable other peripheral functions (SPI and I<sup>2</sup>C) of the IS1870/71 IC on the BM70/71 module by changing the default firmware. For more details, contact local Microchip representatives.

### FIGURE 1-2: BM71 MODULE-BASED SYSTEM BLOCK DIAGRAM



**Note 1:** It is possible to enable other peripheral functions (SPI and I<sup>2</sup>C) of the IS1870/71 IC on the BM70/71 module by changing the default firmware. For more details, contact local Microchip representatives.

Figure 1-3 through Figure 1-6 illustrate the pin diagrams of the BM70/71 module.

FIGURE 1-3: BM70BLE01FC2 PIN DIAGRAM




FIGURE 1-4: BM70BLES1FC2 PIN DIAGRAM




FIGURE 1-5: BM71BLE01FC2 PIN DIAGRAM




FIGURE 1-6: BM71BLES1FC2 PIN DIAGRAM




Table 1-1 provides pin descriptions of the BM70/71 module.

TABLE 1-1: BM70/71 PIN DESCRIPTION

IABLE 1-1.	DIII. 0, 1	TT IIV DEC	CKIPTION				
BM70BLE0 1FC2	BM70BLE S1FC2	BM71BLE 01FC2	BM71BLE S1FC2	Pin Name	Type	Description	
	1		_	GND	Power	Ground reference	
	2		_	GND	Power	Ground reference	
1	3	12	13	GND	Power	Ground reference	
2	4	11,	14	VBAT	Power	Battery input. Voltage range: 1.9V to 3.6V	
		10	_	BK_IN	Power	Buck input. Voltage range: 1.9V to 3.6V	
3	5		_	P2_2	DIO	GPIO, default pull-high input PWM1	
4	6	Γ	_	VDD_IO	Power	I/O positive supply. Do not connect. Ensure VDD_IO and MCU I/O voltage are compatible	
5	7	Γ		VDD_IO	Power	I/O positive supply. Do not connect. Ensure VDD_IO and MCU I/O voltage are compatible	
6	8	1	_	ULPC_O	Power	1.2V programmable ULPC LDO output for AON-logic and retention memory supply. Internal use only, do not connect to other devices	
7	9	-	_	P2_3	DI	GPIO, default pull-high input PWM2	
8	10	<b>-</b>	_	BK_O	Power	1.55V buck output. Internal use only, do not connect to other devices	
	_	13	6	P1_6	DIO	P1_6	
_	_	14	5	P1_7	DIO	P1_7	
9	11	15	15	P2_7/TX_ IND	DIO Al DO	GPIO: P2_7 ADC Input: AD14 TX_IND	
10	12	<u> </u>	_	P1_1	DIO Al	GPIO: P1_1 ADC Input: AD9	
11	13	2	3	P1_2	DIO Al	GPIO, default pull-high input AD10	
12	14	3,	4	P1_3	DIO Al	GPIO, default pull-high input AD11	
13	15	8	11	P0_0	DIO AI DI	GPIO, default pull-high input AD0 UART flow-control CTS	
14	16	— <u>.</u>	_	P1_0	DIO Al	GPIO, default pull-high input AD8	
15	17	6	9	P3_6	DIO DO DO	GPIO, default pull-high input PWM0 UART flow-control RTS	
16	18	16	16	P2_0	DI	System configuration, default pull-high input H: Application mode L: Test mode	
17	19	<u> </u>	_	P2_4	DIO	GPIO, default pull-high input	
18	20	<u> </u>	_	NC <sub>1</sub>		No connection	
Locond:	Λ Λ	nalog		D = Digital		L = Input O = Output	

Legend:A = AnalogD = DigitalI = InputO = Output

## **BM70/71**

TABLE 1-1: BM70/71 PIN DESCRIPTION (CONTINUED)

BM70BLE0 1FC2 (Continued)	BM70BLE S1FC2	BM71BLE 01FC2	BM71BLE S1FC2	Pin Name	Type	Description
19	21	7	10	RST_N	DI	Module Reset (active-low) (internal pull up)
20	22	5	7	HCI_RXD	DI	HCI UART data input
21	23	4	8	HCI_TXD	DO	HCI UART data output
22	24		_	P3_1	DIO	GPIO: P3_1
23	25	<del>-</del> -	_	P3_2	DIO	GPIO: P3_2
24	26	<del>-</del> -	_	P3_3	DIO	GPIO: P3_3
25	27		_	P3_4	DIO	GPIO: P3_4
26	28	<u> </u>	_	P3_5	DIO DO	GPIO, default pull-high input LED1
27	29	<u> </u>	_	P0_7	DIO Al	GPIO, default pull-high input AD7
28	30	9	12	P0_2/LED	DIO Al	P02 AD2
29	31	17	2	GND	Power	Ground reference
_	32	_	_	GND	Power	Ground reference
30	_	1	1	BT_RF	AI	External antenna connection (50 Ohm) Only for BM70BLE01FC2 and BM71BLE01FC2 No connection for BM71BLES1FC2
_	33	_	_	GND	Power	Ground reference

**Legend:** A = Analog D = Digital I = Input O = Output

Table 1-2 provides the hardware features of the BM70/71 module.

Note:

The default firmware of the IS1870/71 IC on the BM70/71 module allows some internal peripheral functionality to be exposed. For details, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542). It is possible to enable other peripheral functions (SPI and I²C) of the IS1870/71 IC on the BM70/71 module by changing the default firmware. For more details, contact local Microchip representatives.

TABLE 1-2: BM70/71 MODULE HARDWARE FEATURES

Feature/ Modules	BM70BL	ES1FC2	C2 BM70BLE01FC2 BM71BLES1FC2 BM71BLE		170BLE01FC2 BM71BLES1FC2		E01FC2	
Configuration	Module H/W	Default IS1870 Firmware	Module H/W	Default IS1870 Firmware	Module H/W	Default IS1871 Firmware	Module H/W	Default IS1871 Firmware
UART	1	1	1	1	1	1	1	1
GPIO (see Note 2)	18	13	18	13	9	4	9	4
12-bit ADC Channels	8	6	8	6	5	3	5	3
PWM	3	2	3	2	1	0	1	0
Total Pins	33	_	30	_	16	_	17	_
On-board Antenna with CAN	Yes	_		_	Yes	_	_	_
No Antenna	_	_	Yes	_	_	_	Yes	_
Government Regulatory RF Certified	Yes	_	_	_	Yes	_	_	_
Size (mm)	12x22x2.4	_	12x15x1.6	_	9x11.5x2.1	_	6x8x1.6	_

Note 1: The GPIO, ADC and PWM numbers used are based on disabling the LED indication and UART Hardware flow-control (RTS/CTS) functionality, see Table 1-1.

**<sup>2:</sup>** For a detailed explanation on GPIO, refer to the "*BM70/71 Bluetooth*® *Low Energy Module User's Guide*" (DS50002542).

## **BM70/71**

Table 1-3 provides the details of the test pads used for the production test on the bottom of the BM70/71 module, see Figure 1-3 through Figure 1-6 for more details.

TABLE 1-3: TEST PADS DETAILS

BM70BLE 01FC2	BM70BLE S1FC2	BM71BLE 01FC2	BM71BLE S1FC2	Pin Name	Туре	Description
TP-1	TP-1	TP-3	TP-3	VCC_PA	Power	1.55V RF PA LDO
TP-2	TP-2	TP-1	TP-1	CLDO_O	Power	1.2V CLDO output
TP-3	TP-3	TP-2	TP-2	VCC_RF	Power	1.28V RF LDO output
_	_	TP-4	TP-4	ULPC_O	Power	1.2V ULPC LDO output
_	_	TP-5	TP-5	BK_O	Power	1.55V buck output

### 2.0 APPLICATION INFORMATION


#### 2.1 Reference Schematics

Figure 2-1 through Figure 2-8 illustrate the BM70/71 module reference circuits for various Stock Keeping Units (SKUs). The GPIOs are configurable and the connection depends on the user's application circuit.


The power input range is 1.9V to 3.6V. If the battery is used, the battery reverse protection circuit is recommended. The VDD IO voltage is same as power

input. If the LED is used, ensure that the voltage is more than 3V to drive the LED. A 1.8V Reset IC is added as an optional circuit to prevent the Flash data crash, when VBAT power is unstable. It is recommended to implement the RF antenna matching circuit, as illustrated in Figure 2-3 and Figure 2-5 to fine tune the antenna impedance matching.


FIGURE 2-1: BM70BLES1FC2 REFERENCE CIRCUIT



#### FIGURE 2-2: BM70BLES1FC2 REFERENCE CIRCUIT



### FIGURE 2-3: BM70BLE01FC2 REFERENCE CIRCUIT



### FIGURE 2-4: BM70BLE01FC2 REFERENCE CIRCUIT





FIGURE 2-5: BM71BLE01FC2 REFERENCE CIRCUIT



### FIGURE 2-6: BM71BLE01FC2 REFERENCE CIRCUIT






FIGURE 2-7: BM71BLES1FC2 REFERENCE CIRCUIT



#### FIGURE 2-8: BM71BLES1FC2 REFERENCE CIRCUIT - OPTIONAL




# 2.2 External Configuration and Programming

The BM70/71 module can be configured and programmed by using an external configuration and programming tool. Figure 2-9 illustrates the minimum signals that must be included on the host PCB for the development.

Configuration and programming modes can be entered according to the system configuration I/O pins. For additional information, refer to **3.4** "System Configuration".

FIGURE 2-9: EXTERNAL CONFIGURATION AND PROGRAMMING




#### 2.3 Host MCU Interface

# 2.3.1 HOST MCU INTERFACE OVER UART


Figure 2-10 and Figure 2-11 illustrate the BM70/71 module to host MCU interface over UART. The Host Control Interface (HCI) UART lines are used to commu-

nicate between the BM70/71 module and MCU. The interface also illustrates the power scheme using a 3.3V Low-Drop Out (LDO) regulator that supply 3.3V to the BM70/71 (BAT\_IN) and MCU VDD. This power scheme ensures that the BM70/71 module and MCU I/O voltages are compatible.

#### FIGURE 2-10: BM70 MODULE TO MCU INTERFACE



#### FIGURE 2-11: BM71 MODULE TO MCU INTERFACE




- Note 1: Ensure that VBAT(=I/O Voltage) and MCU VDD voltages are compatible.
  - **2:** Control and indication ports are configurable. For more details, refer to the "*BM70/71 Bluetooth*® *Low Energy Module User's Guide*" (DS50002542).
  - 3: 10 µF (X5R) and 330 Ohm resistor are required for the BM71 module.
  - 4: BK\_IN connect to VBAT for BM71BLE01FC2.

## 2.3.2 UART READY AFTER EXTERNAL RESET

In MCU applications, the time between Reset and the BM70/71 module UART port ready for Test mode and Application mode after an external Reset (RST\_N)

must be notified. Figure 2-12 illustrates the timing diagram of the BM70/71 module UART port ready for Test mode and Application mode after reset.

FIGURE 2-12: TIMING DIAGRAM OF BM70/71 MODULE UART READY FOR TEST MODE AFTER RESET




## 2.3.3 UART READY AFTER POWER-ON RESET

Figure 2-13 illustrates the timing diagram of the BM70 module UART port ready for Test mode and Application mode after Power-on Reset (POR).

In Application mode, when the BM70/71 module is ready to communicate with the host MCU after reset, the BM70/71 module may have internal status indi-

cated by the status pins, or by a status report UART command. This status pin or status report UART command is sent to inform the MCU that the BM70/71 module is ready for communication.

FIGURE 2-13: TIMING DIAGRAM OF BM70 MODULE UART READY FOR TEST MODE AFTER POWER-ON




## 2.4 Typical Hosted Configuration

Figure 2-14 illustrates the typical hosted configuration for the BM71 module. It also illustrates an application using a coin cell battery at VBAT input. For the BM71

module, a 10  $\mu$ F capacitor (X5R/X7R) is applied to the BAT\_IN pin. Only on the BM71 module, the BK\_IN pin of the module must be connected to the BAT\_IN pin.


#### FIGURE 2-14: BM71 MODULE TYPICAL HOSTED CONFIGURATION



## 2.5 Power-Drop Protection

To prevent the BM70/71 module from disruptions, when the voltage drops to less than 1.9V, an "Open Drain" Reset chip with a delay time of ≤ 10 ms that triggers Reset at 1.8V output voltage is recommended. Figure 2-15 illustrates the Reset circuit block diagram.

FIGURE 2-15: RESET CIRCUIT BLOCK DIAGRAM



$\mathbf{R}$	M	[7	V	/7	1
IJ	17		w	, ,	

NOTES:

### 3.0 MODULE CONFIGURATION

The BM70/71 module features and services can be configured to fit a wide range of application requirements. Refer to the "BM70/71 Bluetooth<sup>®</sup> Low Energy Module User's Guide" (DS50002542) for details of all device behavior along with information on how to configure the IS8170/71 IC on the BM70/71 module. Refer to 3.1"UART Interface" through 3.4"System Configuration" that describe default behavior of the BM70/71 module, which can be easily changed.

#### 3.1 UART Interface

The BM70/71 module UART pins, TXD and RXD, are connected to the UART pins of the host MCU. By default, the UART characteristics are set to a baud rate of 115200, with 8-bit data, 1 stop bit, no parity, and no hardware flow control. These characteristics are config-

urable, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542) for the full description.

#### 3.2 Control and Indication I/O Pins

The I/O pins on the BM70/71 module are configurable as either control or indication signal. The control signals are input to the BM70/71 module and the indication signals are output from the BM70/71 module. Table 3-1 and Table 3-2 provide default pin functions of the default firmware logic in the IS1870/71 IC on the BM70/71 module. For different BM70/71 module application requirements, the I/O pin assignment is configurable and can fit a wide range of application requirements. For additional information related to I/O pin assignment, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542).

TABLE 3-1: CONFIGURATION AND INDICATION I/O ASSIGNMENTS FOR BM70 MODULE

IADEL	•	<del></del>	••••					J. O			MODULE	
PINS	N/C <sup>(1)</sup>	LOW_BATTERY_IND <sup>(1)</sup>	RSSI_IND <sup>(1)</sup>	LINK_DROP <sup>(1)</sup>	UART_RX_IND <sup>(1)</sup>	PAIRING_KEY <sup>(1)</sup>	RF_ACTIVE_IND <sup>(1)</sup>	STATUS1_IND <sup>(1)</sup>	If hardware function is enabled, UART_RTS is fixed to this pin	If hardware function is enabled, UART_CTS is fixed to this pin	If hardware function is enabled, TX_IND is fixed to this pin	If hardware function is enabled, LED0 is fixed to this pin
P1_0												
P3_1			Default									
P3_2				Default								
P3_3					Default							
P3_4						Default						
P0_7		Default										
P1_1								Default				
P2_2	Default											
P2_4	Default											
P3_5	Default											
P3_6									Default			
P0_0										Default		
P2_7											Default	
P0_2												Default

**Note 1:** These signals are part of the remappable hardware functionality and can be input/output on different GPIO pins of the module. Refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542) for details.

TABLE 3-2: CONFIGURATION AND INDICATION I/O ASSIGNMENTS FOR BM71 MODULE

PINS	LOW_BATTERY_IND	RSSI_IND	LINK_DROP	UART_RX_IND	PAIRING_KEY	RF_ACTIVE_IND	STATUS1_IND	STATUS2_IND	If hardware function is enabled, UART_RTS is fixed to this pin	If hardware function is enabled, UART_CTS is fixed to this pin	If hardware function is enabled, TX_IND is fixed to this pin	If hardware function is enabled, LED0 is fixed to this pin
P1_6				Default								
P1_7					Default							
P1_2							Default					
P1_3								Default				
P3_6									Default			
P0_0				<u> </u>						Default		
P2_7											Default	
P0_2												Default

## 3.3 Reset (RST\_N)

The Reset input pin (RST\_N) is used to reset the BM70/71 module with an active-low pulse with a minimum pulse width of 63 ns.

## 3.4 System Configuration

Table 3-3 provides the system configuration settings of the P2\_0 pin that places the BM70/71 module into various operational modes. The P2\_0 pin has an internal pull up.

TABLE 3-3: SYSTEM CONFIGURATION SETTINGS

P2_0	Operational Mode
High	Application mode
Low	Test mode (calibration of the IS1870/71 IC),
	Configuration mode (programming of configuration parameters for default firmware), Firmware update mode (programming of internal flash memory of IS1870/71 IC).

**Note:** For more details and use of these different modes, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542).

### 4.0 ANTENNA

#### 4.1 Antenna Characteristics

## 4.1.1 BM70BLES1FC2 CERAMIC CHIP ANTENNA

The BM70BLES1FC2 module contains an inbuilt ceramic chip antenna. Figure 4-1 illustrates the antenna radiation pattern of the ceramic chip antenna on the BM70BLES1FC2 module.

FIGURE 4-1: BM70BLES1FC2 ANTENNA RADIATION PATTERN




Table 4-1 provides the antenna radiation pattern details of the BM70BLES1FC2 module.

TABLE 4-1: BM70BLES1FC2 ANTENNA RADIATION PATTERN DETAILS

Parameter	Values
Frequency	2450 MHz
Peak Gain	1.63 dBi
Efficiency	71.55%

# 4.1.2 BM71BLES1FC2 CERAMIC CHIP ANTENNA

The BM71BLES1FC2 module contains an inbuilt ceramic chip antenna. Figure 4-2 illustrates the antenna radiation pattern of the ceramic chip antenna on the BM71BLES1FC2 module.

FIGURE 4-2: BM71BLES1FC2 ANTENNA RADIATION PATTERN




Table 4-2 provides the antenna radiation pattern details of the BM71BLES1FC2 module.

TABLE 4-2: BM71BLES1FC2 ANTENNA RADIATION PATTERN DETAILS


Parameter	Values
Frequency	2442 MHz
Peak Gain	0.1 dBi
Efficiency	42.7%

#### 4.2 Antenna Placement

For a Bluetooth wireless product, the antenna placement affects the whole system performance. The antenna requires free space to radiate the RF signals and it cannot be surrounded by the ground plane.

Figure 4-3 illustrates a typical example of the good and poor antenna placement of the BM70BLES1FC2 module on the main application board with the ground plane.


FIGURE 4-3: BM70BLES1FC2 ANTENNA PLACEMENT EXAMPLES



## **BM70/71**

Figure 4-4 illustrates a typical example of the good and poor antenna placement of the BM71BLES1FC2 module on the main application board with the ground plane.

FIGURE 4-4: BM71BLES1FC2 ANTENNA PLACEMENT EXAMPLES



#### 4.3 Antenna Considerations

Table 4-3 provides the part number and manufacturer details of the antenna on the BM70BLES1FC2 module.

TABLE 4-3: BM70BLES1FC2 ANTENNA DETAILS

Description	Manufacturer Part Number	Manufacturer
ANT ANT3216A063R2400A PIFA 2.4 GHZ L3.2W1.6	ANT3216A063R2400A	YAGEO

Table 4-4 provides the part number and manufacturer details of the antenna on the BM71BLES1FC2 module.

### TABLE 4-4: BM71BLES1FC2 ANTENNA DETAILS

Description	Manufacturer Part Number	Manufacturer
ANT ANT3216LL00R2400A 2.4 GHZ L3.2W1.6	ANT3216LL00R2400A	YAGEO


### 4.4 Host PCB Mounting Suggestion

## 4.4.1 BM70BLES1FC2 HOST PCB MOUNTING

Figure 4-5 illustrates the host PCB mounting suggestions for the BM70BLES1FC2 module, and it shows the minimum ground plane area to the left and right of the module for best antenna performance.

While designing the host PCB, the area under the antenna must not contain any top, inner, or bottom copper layer. A low-impedance ground plane ensures the best radio performance (best range, low noise). The ground plane can be extended beyond the minimum recommended as required for the host PCB EMC noise reduction. For best range performance, keep all external metal away by minimum 30 mm from the ceramic chip antenna.

FIGURE 4-5: BM70BLES1FC2 HOST PCB MOUNTING SUGGESTION




## 4.4.2 BM70BLE01FC2 HOST PCB MOUNTING

Figure 4-6 illustrates the mounting suggestions for the BM70BLE01FC2 module and it also shows a connection to UFL connector. A low-impedance ground plane will ensure the best radio performance (best range, low noise).

The pin 30 (BT\_RF) is connected to an external antenna connector, a PCB trace antenna, or a component (ceramic chip) antenna through a host PCB

50 Ohm micro-strip trace. The micro-strip trace can be extended to include passive parts for antenna attenuation padding, impedance matching, or to provide test points. It is recommended that the micro-strip trace must be as short as possible for minimum loss and best impedance matching. If the micro-strip trace is longer, it must be a 50 Ohm controlled impedance.

FIGURE 4-6: BM70BLE01FC2 HOST PCB MOUNTING SUGGESTIONS




## 4.4.3 BM71BLES1FC2 HOST PCB MOUNTING

Figure 4-7 illustrates the mounting suggestions for the BM71BLES1FC2 module. It also shows the area around the antenna, required for the best antenna performance.

The area under the antenna must not contain any top, inner, or bottom copper layer while designing the host PCB. A low-impedance ground plane ensures the best radio performance (best range, low noise). The ground plane can be extended beyond the minimum recommended as required for the host PCB EMC noise reduction. For best range performance, keep all external metal away by minimum 30 mm from the ceramic chip antenna.

FIGURE 4-7: BM71BLES1FC2 HOST MOUNTING SUGGESTION




## 4.4.4 BM71BLE01FC2 HOST PCB MOUNTING

Figure 4-8 illustrates the mounting suggestions for the BM71BLE01FC2 module. It also shows a connection to the UFL connector. A low-impedance ground plane will ensure the best radio performance (best range, low noise).

The pin 1 (BT\_RF) is connected to an external antenna connector, a PCB trace antenna, or a component (ceramic chip) antenna through a host PCB 50 Ohm micro-strip trace. The micro-strip trace can be extended to include passive parts for antenna attenuation padding, impedance matching, or to provide test points. It is recommended that the micro-strip trace must be as short as possible for minimum loss and best impedance matching. If the micro-strip trace is longer, it must be a 50 Ohm controlled impedance.

FIGURE 4-8: BM71BLE01FC2 HOST PCB MOUNTING SUGGESTION





**NOTES:** 

#### 5.0 ELECTRICAL CHARACTERISTICS

This section provides an overview of the BM70/71 module electrical characteristics. Additional information will be provided in future revisions of this document as it become available.

Absolute maximum ratings for the BM70/71 module are listed here. Exposure to the maximum rating conditions for extended periods may affect device reliability. Functional operation of the device at these or any other conditions, above the parameters indicated in the operation listings of this specification, is not implied.

#### **Absolute Maximum Ratings**

Ambient temperature under bias for modules parts ending with 0002	20°C to +70°C
Ambient temperature under bias for modules parts ending with 0B0x	40°C to +85°C
Storage temperature	40°C to +125°C
Voltage on VDD with respect to Vss	-0.3V to +3.6V
Voltage of any digital pin	0.3V to VDD + $0.3 \le 3.9$
Maximum output current sink by any I/O pin	12 mA
Maximum output current sourced by any I/O pin	12 mA

**Note:** Stresses above those listed under "**Absolute Maximum Ratings**" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions, above those indicated in the operation listings of this specification, is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.

Table 5-1 provides the recommended operating conditions of the BM70/71 module.

TABLE 5-1: RECOMMENDED OPERATING CONDITIONS

Symbol	Min.	Тур.	Max.	
	PMU			
VDD (VBAT, BK_IN, AVDD)	1.9V	3.0V	3.6V	
RST_N	1.9V	3.0V	3.6V	
Other I/O	1.9V	_	3.6V	
	GPIO			
V <sub>IH</sub> (Input High Voltage)	0.7 VDD	_	VDD	
V <sub>IL</sub> (Input Low Voltage)	Vss	_	0.3 VDD	
V <sub>OH</sub> (Output High Voltage) (High drive, 12 mA)	0.8 VDD	_	VDD	
V <sub>OL</sub> (Output Low Voltage) (High drive, 12 mA)	Vss	_	0.2 VDD	
Pull up resistance	34 kOhm	48 kOhm	74 kOhm	
Pull down resistance	29 kOhm	47 kOhm	86 kOhm	
Supply Current (see Note 1)				
Peak Tx mode current at VDD=3V, Tx=0 dBm, Buck mode	_	10 mA at +25°C	13 mA at +70°C/+85°C	
Peak Rx mode current at VDD=3V, Buck mode	_	10 mA at +25°C	13 mA at +70°C/+85°C	
"Reduced current consumption" low-power mode current (see <b>Note 2</b> )	_	60 μA at +25°C		
"Shutdown" low-power mode current (see Note 2)	1.0 µA	_	2.9 μΑ	

**Note 1:** The current measurements are characterized across a sample of BM70/71 modules at room temperature (+25°C), unless otherwise noted.

**Note:** For more details on "Analog to Digital Converter (ADC) and Precise Temperature Sensor (PTS) specifications, refer to "IS1870/71 Bluetooth® Low Energy SoC data sheet" (DS60001371).

**<sup>2:</sup>** For more details on "Reduced current consumption" or "Shutdown" low-power modes, refer to the "*BM70/71 Bluetooth*® *Low Energy Module User's Guide*" (DS50002542).

Table 5-2 provides the RF Specifications of the BM70/71 module.

**TABLE 5-2: RF SPECIFICATION** 

Parai	neter	Min.	Тур.	Max.	
		mitter			
Frequency		2402 MHz	_	2480 MHz	
Output Power		_	0 dBm	_	
RF Power Control Ra	ange	-25 dBm	_	3 dBm	
In-band Spurious (N:	±2)	_	-38.5 dBm	_	
In-band Spurious (N:	±3)	_	-43.25 dBm	_	
Modulation Characte Deviation (see <b>Note</b>		_	247 kHz	_	
		Receiver			
Frequency	Frequency		_	2480 MHz	
Sensitivity Level (Inte	erference active)	_	-90 dBm	_	
Interference Perfor-	Co-channel	_	17 dB	_	
mance	mance Adjacent ± 1 MHz Adjacent ± 2 MHz		0 dB	_	
			-25 dB	_	
	Adjacent >= ± 3 MHz	_	-32 dB	_	
Intermodulation Characteristic (n=3,4,5)		_	-37.5 dBm	_	
Maximum Usable Le	vel		0 dBm		

**Note 1:** Tested with a known pattern of '00001111'b being transmitted.

#### 5.1 Current Consumption Details

## 5.1.1 Tx/Rx CURRENT CONSUMPTION DETAILS

Figure 5-1 and Figure 5-2 illustrate the Tx/Rx peak and average current consumption of an advertising event of the IS1870/71 IC on the BM70/71 module.

Figure 5-1 illustrates the Tx/Rx peak current consumption of 12 mA during an advertising event. However, the average current consumption is only around 230  $\mu$ A, while advertising at an interval of approximately 100 ms, see Figure 5-2. This is due to the "Reduced Current Consumption" low-power mode being enabled (configuration parameter - UART RX IND). Reducing the current draw to

approximately 60  $\mu$ A while not actively transmitting the advertisings packets, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542) for more details.

The overall average current consumption is measured with a 3.3V VBAT input, and is affected by the way the IS1870/71 IC on the BM70/71 module has been configured to operate. A low average current value can be achieved by choosing the minimum settings for the advertising interval and connection interval, which meet the data throughput requirements of the intended application. The lower or less frequent the interval time periods, the lower the overall average current to be drawn.

FIGURE 5-1: TX/RX PEAK CURRENT CONSUMPTION OF AN ADVERTISING EVENT





Figure 5-2 provides the oscilloscope screen, which has been captured when the auto operation and low power mode is active on the BM70/71 module. Refer to the "BM70/71 Bluetooth<sup>®</sup> Low Energy Module User's Guide" (DS50002542) for more details on the auto operation.

FIGURE 5-2: TX/RX AVERAGE CURRENT CONSUMPTION WHILE BM70/71 MODULE IS ADVERTISING



For additional information on the current consumption measurements, test conditions, and test environment setup, refer to the "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542). This user guide covers the detailed information about the behavior of the default internal logic of the IS1870/71 IC on the BM70/71 module.

## BM70/71

Table 5-3 provides the average current consumption measurements for the BM70/71 module in Application mode.

TABLE 5-3: BM70/71 APPLICATION MODE CURRENT CONSUMPTION MEASUREMENTS

Test Mode	Interval [ms]	Average Current Consumption
Advertising (see Note 1,2,3)	20	1.061 mA
	50	505 μA
	100	298 μΑ
	500	113 μΑ
	1000	89 μΑ
Connected (see Note 1,2,4)	18.75	2.23 mA
	50	2.13 mA
	100	2.10 mA
	500	83 μΑ
	1000	80 μΑ

- **Note 1:** These measurements are done at an operating temperature of +25°C at 3.3V and are characterized across a sample of BM70/71 modules.
  - 2: These measurements are taken with version 1.06 firmware, loaded into the module with "Reduced Current Consumption" low power mode enabled. For more details on low-power modes and current consumption configuration, refer to "BM70/71 Bluetooth® Low Energy Module User's Guide" (DS50002542).
  - 3: The advertising packet data payload is approximately 15 bytes in length.
  - **4:** The amount of data being transmitted between two peer devices can affect the average current measured. The average current measurements are done with only the necessary Bluetooth packets being exchanged to keep the connection active at the stated interval.

#### 6.0 PHYSICAL DIMENSIONS

#### 6.1 BM70BLES1FC2

Figure 6-1 illustrates the physical dimensions of the BM70BLES1FC2 module.

FIGURE 6-1: BM70BLES1FC2 MODULE DIMENSIONS





Figure 6-2 illustrates the recommended PCB footprint. Ensure that no top copper layer is near the test pin area.

FIGURE 6-2: BM70BLES1FC2 RECOMMENDED PCB FOOTPRINT



#### 6.2 BM70BLE01FC2

Figure 6-3 illustrates the physical dimensions of the BM70BLE01FC2 module.

FIGURE 6-3: BM70BLE01FC2 MODULE DIMENSIONS





Figure 6-4 illustrates the recommended PCB footprint.

#### FIGURE 6-4: BM70BLE01FC2 RECOMMENDED PCB FOOT PRINT



#### 6.3 BM71BLES1FC2

Figure 6-5 illustrates the physical dimensions of the BM71BLES1FC2 module.

FIGURE 6-5: **BM71BLES1FC2 MODULE DIMENSIONS** 





Figure 6-6 illustrates the recommended PCB footprint. Ensure that no top copper layer is near the test pin area.

FIGURE 6-6: BM71BLES1FC2 RECOMMENDED PCB FOOTPRINT



## 6.4 BM71BLE01FC2

Figure 6-7 illustrates the physical dimensions of the BM71BLE01FC2 module.

FIGURE 6-7: BM71BLE01FC2 MODULE DIMENSIONS





Figure 6-8 illustrates the recommended PCB footprint

FIGURE 6-8: BM71BLE01FC2 RECOMMENDED PCB FOOTPRINT



# 7.0 SOLDERING RECOMMENDATIONS


The BM70/71 module is assembled using a standard lead-free, reflow profile, IPC/JEDEC J-STD-020. The BM70/71 module can be soldered to the host PCB by using the standard lead or lead-free solder reflow profiles.

To avoid any damage to the BM70/71 module, follow these recommendations:

- Refer to the "AN233 Solder Reflow Recommendation" (DS00233) document for the soldering reflow recommendations.
- Do not exceed the peak temperature (T<sub>P</sub>) of +260°C.
- · Use no-clean flux solder paste.
- Do not wash the BM70/71 module as moisture can be trapped under the shield.
- Use only one flow. If the PCB requires multiple flows, apply the BM70/71 module on the final flow.

Figure 7-1 illustrates the reflow profile of the BM70/71 module.

FIGURE 7-1: REFLOW PROFILE





**NOTES:** 

#### 8.0 ORDERING GUIDE

Table 8-1 provides the ordering information of the BM70/71 module.

TABLE 8-1: BM70/71 MODULE ORDERING INFORMATION

Module	Microchip IC	Description	Operating Temperature Range	Firmware Version	Antenna	Shield	Pin #	Regulatory Certification	Part Number (see Note 1)
BM70	IS1870SF -102	Bluetooth 4.2 BLE module, (12x15x1.6 mm)	-20°C to +70°C	V1.03	External	No	30	No	BM70BLE01 FC2-0002AA
BM70	IS1870SF -102	Bluetooth 4.2 BLE module, (12x15x2.4 mm)	-20°C to +70°C	V1.03	On board	Yes	33	FCC, IC, CE, MIC, KCC, NCC, SRRC	BM70BLES1 FC2-0002AA
BM71	IS1871SF -102	Bluetooth 4.2 BLE module, (6x8x1.6 mm)	-20°C to +70°C	V1.06	External	No	17	No	BM71BLE01 FC2-0002AA
BM71	IS1871SF -102	Bluetooth 4.2 BLE module, (9x11.5x2.1 mm)	-20°C to +70°C	V1.06	On board	Yes	16	FCC, IC, CE, MIC, KCC, NCC, SRRC	BM71BLES1 FC2-0002AA
ВМ70	IS1870SF -202	Bluetooth 4.2 BLE module, (12x15x1.6 mm)	-40°C to +85°C	V1.06	External	No	30	No	BM70BLE01 FC2-0B03A A
BM70	IS1870SF -202	Bluetooth 4.2 BLE module, (12x15x2.4 mm)	-40°C to +85°C	V1.06	On board	Yes	33	FCC, IC, CE, MIC, KCC, NCC, SRRC	BM70BLES1 FC2-0B03A A
BM71	IS1871SF -202	Bluetooth 4.2 BLE module, (6x8x1.6 mm)	-40°C to +85°C	V1.06	External	No	17	No	BM71BLE01 FC2-0B02A A
BM71	IS1871SF -202	Bluetooth 4.2 BLE module, (9x11.5x2.1 mm)	-40°C to +85°C	V1.06	On board	Yes	16	FCC, IC, CE, MIC, KCC, NCC, SRRC	BM71BLES1 FC2-0B02A A

**Note 1:** With the introduction of the IS187xSF-202 IC, the PC tools provided by Microchip, which change/control Bluetooth operation have been revised.

The correct tool version must be paired with the applicable module/IC part number.

 $\label{eq:all-module-parts} \textbf{All module parts ending with BM7xBLEX1FC2-0BxxAA must use the PC tools ending with 0BxxAA.}$ 

All module parts ending with BM7xBLEX1FC2-0002AA must use the PC tools ending with 0002AA.



**NOTES:** 

# APPENDIX A: CERTIFICATION NOTICES

The BM70 module (BM70BLES1FC2) has received the regulatory approval for the following countries:

BT SIG/QDID:74246

United States/FCC ID: A8TBM70ABCDEFGH

Canada

- IC ID: 12246A-BM70BLES1F2

- HVIN: BM70BLES1F2

Europe/CE

• Japan/MIC: 202-SMD069

• Korea/KCC: MSIP-CRM-mcp-BM70BLES1FC2

Taiwan/NCC No: CCAN15LP0500T1China/SRRC: CMIIT ID: 2015DJ7135

The BM71 module (BM71BLES1FC2) has received the regulatory approval for the following countries:

BT SIG/QDID:74246

United States/FCC ID: A8TBM71S2

Canada

IC ID: 12246A-BM71S2HVIN: BM71BLES1FC2

· Europe/CE

• Japan/MIC: 005-101150

Korea/KCC: MSIP-CRM-mcp-BM71BLES1FC2

Taiwan/NCC No: CCAN16LP0010T5China/SRRC: CMIIT ID: 2016DJ2787

#### A.1 REGULATORY APPROVAL

This section outlines the regulatory information for the BM70/71 module for the following countries:

- · United States
- Canada
- Europe
- Japan
- Korea
- Taiwan
- China
- · Other Regulatory Jurisdictions

#### A.1.1 UNITED STATES

The BM70/71 module has received Federal Communications Commission (FCC) CFR47 Telecommunications, Part 15 Subpart C "Intentional Radiators" modular approval in accordance with Part 15.212 Modular Transmitter approval. Modular approval allows the end user to integrate the BM70/71 module into a finished product without obtaining subsequent and separate FCC approvals for intentional radiation, provided no changes or modifications are made to the module circuitry. Changes or modifications could void the user's authority to operate the equipment. The end

user must comply with all of the instructions provided by the Grantee, which indicate installation and/or operating conditions necessary for compliance.

The finished product is required to comply with all applicable FCC equipment authorizations regulations, requirements and equipment functions not associated with the transmitter module portion. For example, compliance must be demonstrated to regulations for other transmitter components within the host product; to requirements for unintentional radiators (Part 15 Subpart B "Unintentional Radiators"), such as digital devices, computer peripherals, radio receivers, etc.; and to additional authorization requirements for the non-transmitter functions on the transmitter module (i.e., Verification, or Declaration of Conformity) (e.g., transmitter modules may also contain digital logic functions) as appropriate.

# A.1.2 LABELING AND USER INFORMATION REQUIREMENTS

The BM70/71 module has been labeled with its own FCC ID number, and if the FCC ID is not visible when the module is installed inside another device, then the outside of the finished product into which the module is installed must also display a label referring to the enclosed module. This exterior label can use wording as follows:

For the BM70 module:

Contains Transmitter Module

FCC ID:A8TBM70ABCDEFGH

or

Contains FCC ID: A8TBM70ABCDEFGH

This device complies with Part 15 of the FCC Rules. Operation is subject to the following two conditions: (1) this device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation

For the BM71 module:

Contains Transmitter Module

FCC ID: A8TBM71S2

or

Contains FCC ID: A8TBM71S2

This device complies with Part 15 of the FCC Rules. Operation is subject to the following two conditions: (1) this device may not cause harmful interference, and (2) this device must accept any interference received, including interference that may cause undesired operation

On the BM71 module, due to the limited module size (9.0 mm x 11.5 mm), the FCC identifier is displayed in the data sheet only and it cannot be displayed on the module label.

A user's manual for the finished product should include the following statement:

This equipment has been tested and found to comply with the limits for a Class B digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference in a residential installation. This equipment generates, uses and can radiate radio frequency energy, and if not installed and used in accordance with the instructions, may cause harmful interference to radio communications. However, there is no guarantee that interference will not occur in a particular installation. If this equipment does cause harmful interference to radio or television reception, which can be determined by turning the equipment off and on, the user is encouraged to try to correct the interference by one or more of the following measures:

- · Reorient or relocate the receiving antenna
- Increase the separation between the equipment and receiver
- Connect the equipment into an outlet on a circuit different from that to which the receiver is connected
- Consult the dealer or an experienced radio/TV technician for help

Additional information on labeling and user information requirements for Part 15 devices can be found in KDB Publication 784748, which is available at the FCC Office of Engineering and Technology (OET) Laboratory Division Knowledge Database (KDB) <a href="http://apps.fcc.gov/oetcf/kdb/index.cfm">http://apps.fcc.gov/oetcf/kdb/index.cfm</a>.

#### A.1.3 RF EXPOSURE

All transmitters regulated by FCC must comply with RF exposure requirements. KDB 447498 General RF Exposure Guidance provides guidance in determining whether proposed or existing transmitting facilities, operations or devices comply with limits for human exposure to Radio Frequency (RF) fields adopted by the Federal Communications Commission (FCC).

From the FCC Grant: Output power listed is conducted. This grant is valid only when the module is sold to OEM integrators and must be installed by the OEM or OEM integrators. This transmitter is restricted for use with the specific antenna(s) tested in this application for Certification and must not be co-located or operating in conjunction with any other antenna or transmitters within a host device, except in accordance with FCC multi-transmitter product procedures. This module is approved for installation into mobile or/and portable host platforms

#### A.1.4 HELPFUL WEB SITES

Federal Communications Commission (FCC): http://www.fcc.gov

FCC Office of Engineering and Technology (OET) Laboratory Division Knowledge Database (KDB): http://apps.fcc.gov/oetcf/kdb/index.cfm.

#### A.2 Canada

The BM70/71 module has been certified for use in Canada under Industry Canada (IC) Radio Standards Specification (RSS) RSS-247 and RSS-Gen. Modular approval permits the installation of a module in a host device without the need to recertify the device.

## A.2.1 LABELING AND USER INFORMATION REQUIREMENTS

Labeling Requirements for the Host Device (from Section 3.1, RSS-Gen, Issue 4, November 2014): The host device shall be properly labeled to identify the module within the host device.

On BM71 module, due to the limited module size (9.0 mm x 11.5 mm) the IC identifier is displayed in the data sheet only and cannot be displayed on the module label.

The Industry Canada certification label of a module shall be clearly visible at all times when installed in the host device, otherwise the host device must be labeled to display the Industry Canada certification number of the module, preceded by the words "Contains transmitter module", or the word "Contains", or similar wording expressing the same meaning, as follows:

Contains transmitter module IC: 12246A-BM70BLES1F2

For the BM71 module:

For the BM70 module:

Contains transmitter module

IC: 12246A-BM71S2

User Manual Notice for License-Exempt Radio Apparatus (from Section 8.4, RSS-Gen, Issue 4, November 2014): User manuals for license-exempt radio apparatus shall contain the following or equivalent notice in a conspicuous location in the user manual or alternatively on the device or both:

This device complies with Industry Canada license-exempt RSS standard(s). Operation is subject to the following two conditions: (1) this device may not cause interference, and (2) this device must accept any interference, including interference that may cause undesired operation of the device.

Le présent appareil est conforme aux CNR d'Industrie Canada applicables aux appareils radio exempts de licence. L'exploitation est autorisée aux deux conditions suivantes: (1) l'appareil ne doit pas produire de brouillage, et (2) l'utilisateur de l'appareil doit accepter tout brouillage radioélectrique subi, même si le brouillage est susceptible d'en compromettre le fonctionnement.

Transmitter Antenna (from Section 8.3, RSS-Gen, Issue 4, November 2014): User manuals for transmitters shall display the following notice in a conspicuous location:

Under Industry Canada regulations, this radio transmitter may only operate using an antenna of a type and maximum (or lesser) gain approved for the transmitter by Industry Canada. To reduce potential radio interference to other users, the antenna type and its gain should be so chosen that the equivalent isotropically radiated power (e.i.r.p.) is not more than that necessary for successful communication.

Conformément à la réglementation d'Industrie Canada, le présent émetteur radio peut fonctionner avec une antenne d'un type et d'un gain maximal (ou inférieur) approuvé pour l'émetteur par Industrie Canada. Dans le but de réduire les risques de brouillage radioélectrique à l'intention des autres utilisateurs, il faut choisir le type d'antenne et son gain de sorte que la puissance isotrope rayonnée équivalente (p.i.r.e.) ne dépasse pas l'intensité nécessaire à l'établissement d'une communication satisfaisante.

The preceding notice may be affixed to the device instead of displayed in the user manual.

#### A.2.2 RF EXPOSURE

All transmitters regulated by IC must comply with RF exposure requirements listed in RSS-102 - Radio Frequency (RF) Exposure Compliance of Radio communication Apparatus (All Frequency Bands).

#### A.2.3 HELPFUL WEB SITES

Industry Canada: http://www.ic.gc.ca/

#### A.3 Europe

The BM70/71 module is an R&TTE Directive assessed radio module that is CE marked and has been manufactured and tested with the intention of being integrated into a final product.

The BM70/71 module has been tested to R&TTE Directive 1999/5/EC Essential Requirements for Health and Safety (Article (3.1(a)), Electromagnetic Compatibility (EMC) (Article 3.1(b)), and Radio (Article 3.2) and are summarized in Table A-1/Table A-2. A Notified Body Opinion has also been issued.

The R&TTE Compliance Association provides guidance on modular devices in the document "*Technical Guidance Note 01*" which is available for download from the following location:

http://www.rtteca.com/html/download area.htm.

To maintain conformance to the testing listed in Table A-1/Table A-2: European Compliance Testing, the module shall be installed in accordance with the installation instructions in this data sheet and shall not be modified.

When integrating a radio module into a completed product the integrator becomes the manufacturer of the final product and is therefore responsible for demonstrating compliance of the final product with the essential requirements of the R&TTE Directive.

## A.3.1 LABELING AND USER INFORMATION REQUIREMENTS

The label on the final product which contains the BM70/71 module must follow CE marking requirements. The R&TTE Compliance Association **Technical Guidance Note 01** provides guidance on final product CE marking.

#### A.3.2 ANTENNA REQUIREMENTS

From the R&TTE Compliance Association document Technical Guidance Note 01.

Provided the integrator installing an assessed radio module with an integral or specific antenna and installed in conformance with the radio module manufacturer's installation instructions requires no further evaluation. Under Article 3.2 of the R&TTE Directive and does not require further involvement of an R&TTE Directive Notified Body for the final product. [Section 2.2.4]

The European Compliance Testing listed in Table A-1 and Table A-2 were performed using the integral ceramic chip antenna.

TABLE A-1: EUROPEAN COMPLIANCE TESTING (BM70 MODULE)

Certification	Standards	Article	Laboratory	Report Number
Safety	EN60950-1:2006/A11:2009/A1:2010/ A12:2011/A2:2013	[3.1(a)]		10051261 003
Health	EN62479:2010		TI N /	10053580 001
EMC	EN301489-1 V1.9.2	[3.1(b)]	TUV Rheinland	
	EN301489-17 V2.2.1		raiciniana	10051137 002
Radio	EN300328 V1.9.1	(3.2)		10053580 001
Notified Body Opinion	C€0197	_		10048935 001

TABLE A-2: EUROPEAN COMPLIANCE TESTING (BM71 MODULE)

Certification	Standards	Article	Laboratory	Report Number
Safety	EN60950-1:2006/A11:2009/A1:2010/ A12:2011/A2:2013	[3.1(a)]		10053210 001
Health	EN62479:2010		TID.	10053433 001
EMC	EN301489-1 V1.9.2	[3.1(b)]	TUV Rheinland	
	EN301489-17 V2.2.1		Talcillana	10052964 001
Radio	EN300328 V1.9.1	(3.2)		10053433 001
Notified Body Opinion	C€0197	_		10048936 001

#### A.3.3 HELPFUL WEB SITES

A document that can be used as a starting point in understanding the use of Short Range Devices (SRD) in Europe is the European Radio Communications Committee (ERC) Recommendation 70-03 E, which can be downloaded from the European Radio Communications Office (ERO) at: http://www.ero.dk/. Additional helpful web sites are:

- Radio and Telecommunications Terminal Equipment (R&TTE):
   http://ec.europa.eu/enterprise/rtte/index\_en.htm
- European Conference of Postal and Telecommunications Administrations (CEPT):

http://www.cept.org

- European Telecommunications Standards Institute (ETSI):
  - http://www.etsi.org
- European Radio Communications Office (ERO): http://www.ero.dk
- The Radio and Telecommunications Terminal Equipment Compliance Association (R&TTE CA): http://www.rtteca.com

#### A.4 Japan

The BM70/71 module has received type certification and is labeled with its own technical conformity mark and certification number as required to conform to the technical standards regulated by the Ministry of Internal Affairs and Communications (MIC) of Japan pursuant to the Radio Act of Japan.

Integration of this module into a final product does not require additional radio certification provided installation instructions are followed and no modifications of the module are allowed. Additional testing may be required:

- If the host product is subject to electrical appliance safety (for example, powered from an AC mains), the host product may require Product Safety Electrical Appliance and Material (PSE) testing. The integrator should contact their conformance laboratory to determine if this testing is required
- There is an voluntary Electromagnetic Compatibility (EMC) test for the host product administered by VCCI: http://www.vcci.jp/vcci\_e/index.html

## A.4.1 LABELING AND USER INFORMATION REQUIREMENTS

The label on the final product which contains the BM70/71 module must follow Japan marking requirements. The integrator of the module should refer to the labeling requirements for Japan available at the Ministry of Internal Affairs and Communications (MIC) website.

The BM70 module is labeled with its own technical conformity mark and certification number. The final product in which this module is being used must have a label referring to the type certified module inside:



On BM71 module, due to the limited module size (9.0 mm x 11.5 mm) the Japan identifier is displayed in the data sheet only and cannot be displayed on the module label. The final product in which this module is being used must have a label referring to the type certified module inside:



**HELPFUL WEB SITES** 

Ministry of Internal Affairs and Communications (MIC): http://www.tele.soumu.go.jp/e/index.htm

Association of Radio Industries and Businesses (ARIB): http://www.arib.or.jp/english/

#### A.5 Korea

The BM70/71 module has received certification of conformity in accordance with the Radio Waves Act. Integration of this module into a final product does not require additional radio certification provided installation instructions are followed and no modifications of the module are allowed.

## A.5.1 LABELING AND USER INFORMATION REQUIREMENTS

The label on the final product which contains the BM70/71 module must follow KC marking requirements. The integrator of the module should refer to the labeling requirements for Korea available on the Korea Communications Commission (KCC) website.

The BM70 module is labeled with its own KC mark. The final product requires the KC mark and certificate number of the module:



On the BM71 module, due to the limited module size (9.0 mm x 11.5 mm) the KC mark and identifier is displayed in the data sheet only and cannot be displayed on the module label. The final product requires the KC mark and certificate number of the module:



#### A.5.2 HELPFUL WEB SITES

Korea Communications Commission (KCC): http://www.kcc.go.kr

National Radio Research Agency (RRA): http://rra.go.kr

#### A.6 Taiwan

The BM70/71 module has received compliance approval in accordance with the Telecommunications Act. Customers seeking to use the compliance approval in their product should contact Microchip Technology sales or distribution partners to obtain a Letter of Authority.

Integration of this module into a final product does not require additional radio certification provided installation instructions are followed and no modifications of the module are allowed.

## A.6.1 LABELING AND USER INFORMATION REQUIREMENTS

The BM70 module is labeled with its own NCC mark and certificate number as below:



On the BM71 module, due to the limited module size (9.0 mm x 11.5 mm) the NCC mark and identifier is displayed in the data sheet only and cannot be displayed on the module label.



The user's manual should contain following warning (for RF device) in traditional Chinese:

#### 注意!

依據 低功率電波輻射性電機管理辦法

第十二條 經型式認證合格之低功率射頻電機, 非經許可,

公司、商號或使用者均不得擅自變更頻率、加大功率或 變更原設計

之特性及功能。

第十四條 低功率射頻電機之使用不得影響飛航安全及 干擾合法通信;

經發現有干擾現象時,應立即停用,並改善至無干擾時 方得繼續使用。

前項合法通信,指依電信規定作業之無線電信。

低功率射頻電機須忍受合法通信或工業、科學及醫療用 電波輻射性

電機設備之干擾。

#### A.6.2 HELPFUL WEB SITES

National Communications Commission (NCC): http://www.ncc.gov.tw

#### A.7 China

The BM70/71 module has received certification of conformity in accordance with the China MIIT Notice 2014-01 of State Radio Regulation Committee (SRRC) certification scheme. Integration of this module into a final product does not require additional radio certification, provided installation instructions are followed and no modifications of the module are allowed.

# A.7.1 LABELING AND USER INFORMATION REQUIREMENTS

The BM70 module is labeled with its own CMIIT ID as follows:

## CMIIT ID: 2015DJ7135

When Host system is using an approved Full Modular Approval (FMA) radio: The host must carry a label containing the statement "This device contains SRRC approved Radio module CMIIT ID: 2015DJ7135".

On the BM71 module, due to the limited module size (9.0 mm x 11.5 mm) the CMIIT ID is displayed in the data sheet only and cannot be displayed on the module label:

## CMIIT ID: 2016DJ2787

When Host system is using an approved Full Modular Approval (FMA) radio: The host must carry a label containing the statement "This device contains SRRC approved Radio module CMIIT ID: 2016DJ2787".

#### A.8 Other Regulatory Jurisdictions

Should other regulatory jurisdiction certification be required by the customer, or the customer need to recertify the module for other reasons, contact Microchip for the required utilities and documentation.

#### APPENDIX B: REVISION HISTORY

#### **Revision A (October 2015)**

This is the initial released version of the document.

#### **Revision B (October 2015)**

This revision includes the following changes as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE B-1: MAJOR SECTION UPDATES

Section	Update Description
"Features"	This section is updated with certification informations. The data from this section has been reformatted and distributed in other sections.
"MAC/Baseband/Higher Layer Features", "Power Management", "Operating Conditions",and FIGURE 2: "BM71 MODULE"	These sections are newly added.
"General Description"	This section was previously placed in chapter 1 and has been moved here.
1.0 "Device Overview"	Table 1-2, Table 1-4, and Table 1-5 are added.
2.0 "Application Information"	This chapter contains information that was previously located in Appendix A and Electrical Characteristics.
8.0 "Ordering Guide"	Table 8-1 is updated with Y-axis information and certification information.
Appendix B: "Revision History"	This section is updated with images for the Certification Marking and their numbers. The regulatory information is updated to be the latest.
5.0 "Electrical Characteristics"	Table 5-3 is added

#### **Revision C (November 2015)**

Updated Appendix A: "Certification Notices".

#### Revision D (March 2016)

This revision includes the following changes as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE D-1: MAJOR SECTION UPDATES

Section	Update Description
1.1 "Interface Description"	This section is updated with a note. Updated Figure 1-1, Figure 1-2, Figure 1-6
2.1 "Reference Schematics"	Figure 2-1 through Figure 2-8, Figure 2-10, Figure 5-1, Figure 5-2, Figure 2-11, Figure 4-1 and Table 4-1, Table 8-1
"Absolute Maximum Ratings"	Updated this section.
5.1.1 "Tx/Rx current consumption details"	Updated this section with new content.
8.0 "Ordering Guide"	This section is updated with a note.
Appendix A: "Certification Notices"	Content has been updated

## **BM70/71**

### Revision E (January 2017)

This revision includes the following changes as well as minor updates to text and formatting, which were incorporated throughout the document.

TABLE E-1: MAJOR SECTION UPDATES

Section	Update Description
"Features"	Updated this section.
"MAC/Baseband/Higher Layer Features"	Updated this section.
"Power Management"	Updated the average current details.
"Operating Conditions"	Updated the operating temperature details.
1.0 "Device Overview"	Updated Figure 1-1, Figure 1-2, Table 1-1 and Table 1-2 Deleted Table 1-4
2.0 "Application Information"	Updated Figure 2-9 through Figure 2-11 and Figure 2-14
3.0 "Module Configuration"	Added Table 3-2 and updated this section.
4.3 "Antenna Considerations"	Added new section.
5.0 "Electrical Characteristics"	Updated ambient temperature details for part numbers ending with 0002 and 0B0x. Deleted Table 5-2. Updated Table 5-1, Table 5-3 Added Table 5-2
8.0 "Ordering Guide"	Updated Table 8-1
Appendix A: "Certification Notices"	Updated this section.

#### THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com. Under "Support", click on "Customer Change Notification" and follow the registration instructions.

#### **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- · Distributor or Representative
- · Local Sales Office
- Field Application Engineer (FAE)
- · Technical Support

Customers should contact their distributor, representative or Field Application Engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://microchip.com/support



**NOTES:** 

#### Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- · Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

Microchip received ISO/TS-16949:2009 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona; Gresham, Oregon and design centers in California and India. The Company's quality system processes and procedures are for its PIC® MCUs and dsPIC® DSCs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

# QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV = ISO/TS 16949=

#### **Trademarks**

The Microchip name and logo, the Microchip logo, AnyRate, AVR, AVR logo, AVR Freaks, BeaconThings, BitCloud, CryptoMemory, CryptoRF, dsPIC, FlashFlex, flexPWR, Heldo, JukeBlox, KEELOQ, KEELOQ logo, Kleer, LANCheck, LINK MD, maXStylus, maXTouch, MediaLB, megaAVR, MOST, MOST logo, MPLAB, OptoLyzer, PIC, picoPower, PICSTART, PIC32 logo, Prochip Designer, QTouch, RightTouch, SAM-BA, SpyNIC, SST, SST Logo, SuperFlash, tinyAVR, UNI/O, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

ClockWorks, The Embedded Control Solutions Company, EtherSynch, Hyper Speed Control, HyperLight Load, IntelliMOS, mTouch, Precision Edge, and Quiet-Wire are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, Anyln, AnyOut, BodyCom, chipKIT, chipKIT logo, CodeGuard, CryptoAuthentication, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, EtherGREEN, In-Circuit Serial Programming, ICSP, Inter-Chip Connectivity, JitterBlocker, KleerNet, KleerNet logo, Mindi, MiWi, motorBench, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PureSilicon, QMatrix, RightTouch logo, REAL ICE, Ripple Blocker, SAM-ICE, Serial Quad I/O, SMART-I.S., SQI, SuperSwitcher, SuperSwitcher II, Total Endurance, TSHARC, USBCheck, VariSense, ViewSpan, WiperLock, Wireless DNA, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

 $\ensuremath{\mathsf{SQTP}}$  is a service mark of Microchip Technology Incorporated in the U.S.A.

Silicon Storage Technology is a registered trademark of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2015-2017, Microchip Technology Incorporated, All Rights Reserved.

ISBN: 978-1-5224-1287-8



## **Worldwide Sales and Service**

#### **AMERICAS**

Corporate Office 2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support:

http://www.microchip.com/ support

Web Address:

www.microchip.com

Atlanta Duluth, GA Tel: 678-957-9614 Fax: 678-957-1455

Austin, TX Tel: 512-257-3370

**Boston**Westborough, MA
Tel: 774-760-0087
Fax: 774-760-0088

Chicago Itasca, IL Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit Novi, MI

Tel: 248-848-4000 **Houston, TX** Tel: 281-894-5983

Indianapolis Noblesville, IN Tel: 317-773-8323

Tel: 317-773-8323 Fax: 317-773-5453 Tel: 317-536-2380

Los Angeles Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Tel: 951-273-7800 **Raleigh, NC** Tel: 919-844-7510

New York, NY Tel: 631-435-6000

**San Jose, CA** Tel: 408-735-9110 Tel: 408-436-4270

**Canada - Toronto** Tel: 905-695-1980 Fax: 905-695-2078

#### ASIA/PACIFIC

Asia Pacific Office Suites 3707-14, 37th Floor Tower 6, The Gateway Harbour City, Kowloon

Hong Kong Tel: 852-2943-5100 Fax: 852-2401-3431

Australia - Sydney Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

**China - Beijing** Tel: 86-10-8569-7000 Fax: 86-10-8528-2104

**China - Chengdu** Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

**China - Chongqing** Tel: 86-23-8980-9588 Fax: 86-23-8980-9500

**China - Dongguan** Tel: 86-769-8702-9880

**China - Guangzhou** Tel: 86-20-8755-8029

**China - Hangzhou** Tel: 86-571-8792-8115 Fax: 86-571-8792-8116

**China - Hong Kong SAR** Tel: 852-2943-5100 Fax: 852-2401-3431

**China - Nanjing** Tel: 86-25-8473-2460 Fax: 86-25-8473-2470

**China - Qingdao** Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

**China - Shanghai** Tel: 86-21-3326-8000 Fax: 86-21-3326-8021

**China - Shenyang** Tel: 86-24-2334-2829

Fax: 86-24-2334-2393 **China - Shenzhen** 

Tel: 86-755-8864-2200 Fax: 86-755-8203-1760

China - Wuhan Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

**China - Xian** Tel: 86-29-8833-7252 Fax: 86-29-8833-7256

#### ASIA/PACIFIC

**China - Xiamen** Tel: 86-592-2388138 Fax: 86-592-2388130

**China - Zhuhai** Tel: 86-756-3210040 Fax: 86-756-3210049

India - Bangalore Tel: 91-80-3090-4444 Fax: 91-80-3090-4123

India - New Delhi Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

**India - Pune** Tel: 91-20-3019-1500

**Japan - Osaka** Tel: 81-6-6152-7160 Fax: 81-6-6152-9310

**Japan - Tokyo** Tel: 81-3-6880- 3770 Fax: 81-3-6880-3771

**Korea - Daegu** Tel: 82-53-744-4301 Fax: 82-53-744-4302

**Korea - Seoul** Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

Malaysia - Kuala Lumpur Tel: 60-3-6201-9857 Fax: 60-3-6201-9859

**Malaysia - Penang** Tel: 60-4-227-8870 Fax: 60-4-227-4068

Philippines - Manila Tel: 63-2-634-9065 Fax: 63-2-634-9069

**Singapore**Tel: 65-6334-8870
Fax: 65-6334-8850

**Taiwan - Hsin Chu** Tel: 886-3-5778-366 Fax: 886-3-5770-955

Taiwan - Kaohsiung Tel: 886-7-213-7830

**Taiwan - Taipei** Tel: 886-2-2508-8600 Fax: 886-2-2508-0102

Thailand - Bangkok Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### **EUROPE**

Austria - Wels Tel: 43-7242-2244-39 Fax: 43-7242-2244-393

**Denmark - Copenhagen** Tel: 45-4450-2828 Fax: 45-4485-2829

Finland - Espoo Tel: 358-9-4520-820

France - Paris Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

France - Saint Cloud Tel: 33-1-30-60-70-00

Germany - Garching Tel: 49-8931-9700 Germany - Haan Tel: 49-2129-3766400 Germany - Heilbronn

Tel: 49-7131-67-3636 **Germany - Karlsruhe** Tel: 49-721-625370

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

**Germany - Rosenheim** Tel: 49-8031-354-560

**Israel - Ra'anana** Tel: 972-9-744-7705

Italy - Milan Tel: 39-0331-742611 Fax: 39-0331-466781

**Italy - Padova** Tel: 39-049-7625286

**Netherlands - Drunen** Tel: 31-416-690399 Fax: 31-416-690340

Norway - Trondheim Tel: 47-7289-7561

Poland - Warsaw
Tel: 48-22-3325737

Romania - Bucharest Tel: 40-21-407-87-50

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**Sweden - Gothenberg** Tel: 46-31-704-60-40

Sweden - Stockholm Tel: 46-8-5090-4654

**UK - Wokingham** Tel: 44-118-921-5800 Fax: 44-118-921-5820